



ESSENTIAL DRUGS COMPANY LIMITED

395-397, Tejgaon Industrial Area,

Dhaka-1208

Corrigendum Notice

Corrigendum to our Tender Notice No. EDCL(Bogura)/PUR/PT/2026/335 Dated 13/09/2026 for Supply, Installation, Testing , Commissioning , Setup and Renovation of HVAC System of Microbiology Lab at EDCL, Bogura Plant in the following manner:

01. The above tender will be dropped and opened on 25/10/2026 instead of 06/10/2026.

02. Earnest Money will be 2.5% instead of 5%.

03. Some of the Terms & conditions of the above Tender have been changed.


(Details as per Tender Schedule)

Note: The above Tender was published earlier in The Daily Deenkal and The Daily New Age on 14/09/2026.

পত্রিকায় প্রকাশের সাথে সাথেই
একখানা সৌজন্য কপি অত্র দফতরে
প্রেরণ করার জন্য অনুরোধ করা হইল।

General Manager (cc)
Procurement Department
For: Managing Director

o/c



ESSENTIAL DRUGS COMPANY LIMITED

395-397 Tejgaon Industrial Area, Dhaka.

Subject: Minutes of the Pre-Bid Meeting on Renovation Works and Supply, Installation, Testing & Commissioning of HVAC System of Microbiology Lab at General Plant, EDCL, Thanthania, Bogura.

Date : 30/09/2026
Venue : Conference Room of EDCL Dhaka.
Presided by : Managing Director, EDCL
Participants : List enclosed.

Following points were discussed and Resolutions were taken:

A. Technical Part:

Sl. No.	Discussions	Resolutions
1	Type of AHU	AHU as mentioned in BOQ will be DX Type.
2	Segregation of items in BOQ	All Items of BOQ will be segregated into 02 (two) parts, viz. (a) Imported Parts, (b) Local Parts. Accordingly BOQ will be revised. Bidder(s) will quote import part in USD and local part in BDT.
3	Room Data Sheet (RDS).	Room Data Sheet (RDS) will be prepared for the Microbiology Laboratory and to be enclosed with the BOQ.
4	Sandwitch Panels (BOQ Part – B, Sl. No.: 1)	Sandwitch Panel thickness will be 50 mm for Ceiling and 40 mm for Wall.
5	Input Power of Dynamic Pass Box (BOQ Part – B, Sl. No.: 4)	Input Power of Dynamic Pass Box will be 250 Watt instead of 250 Kw.
6	Aluminum Door-Corner (BOQ Part – B, Sl. No.: 10)	Quantities of Aluminum Door-Corner will be 52 instead of 30.
7	Supervision & Installation Cost and Transport Cost (BOQ Part – B, Sl. No.: 12 and 13)	To be omitted from BOQ.
8	Dehumidifier, Dust Collector, Air-Cooled Screw Chiller, Pump etc. mentioned in Tender Document (but not in BOQ) are not required for the project.	Dehumidifier, Dust Collector, Air-Cooled Screw Chiller, Pump etc. mentioned in BOQ which are not required for the project will be ommited.
9	Site Visit	Bidders were advised to visit the site (EDCL, Bogura) before tender dropping to have a clear idea and concept about the project.



22/10/26
22/10/26

B. Commercial Part:

S.I No.	Discussion	Resolutions
1.	All bidders requested to extent the dropping date.	Dropping date has been extended up to 25.10.2026.
2.	All bidders request to decrease the Earnest Money.	Earnest money will be 2.5% instead of 5%

As there was no more issue for discussion, the meeting ended with the thanks of the chair.

